

# FLOOR FALSEWORK DESIGN CALCULATION

# SYSTEM: CUP LOCK SYSTEM

PROJECT: PROPOSED MOSQUE (G+1) & SERVICE BLOCK AT WADI AL SAFA 5, DUBAI, U.A.E.

<u>CLIENT:</u> MR. ABDUL GAFFAR SYED MOHD AL HASHIMI

<u>CONSULTANT:</u> CITY SPACE ENGINEERING CONSULTANCY.

MAIN CONTRACTOR: ARIFCO BUILDING CONTRACTING L.L.C.

REFERENCE DWG.NO.: DBC/H/2020/6501 (ROOF SLAB)

PREPARED BY: ENGR. A.MANALANSAN CHECKED BY: ENGR. B. GUNABE



DATE: 29/03/2020

#### PROJECT : PROPOSED MOSQUE (G+1) & SERVICE BLOCK AT WADI AL SAFA 5, DUBAI, U.A

## REFERENCE DWG NO.: DBC/H/2020/6501 (ROOF SLAB)

# SLAB DEPTH 300mm

### A. Slab Falsework

Cuplock Support System- (Grid 1.800x1.30)

### **Slab Falsework**


	q	=	9.00 kN/M <sup>2</sup>
Construction live load		=	1.50 kN/M <sup>2</sup>
Concrete	.30x25.0 kN/m2	=	7.50 kN/M <sup>2</sup>
Live load	=		1.50 kN/M <sup>2</sup>
Self weight of Formwork		=	0.50 kN/M <sup>2</sup>
Self weight of Concrete	=	:	25.0 kN/m <sup>3</sup>

### B. Plywood Sheathing

Plywood thickness	=	18 mm
Normal Size	=	1220 x 2440 mm
Concrete Pressure	=	9.00 kN/M²

#### See Deflection Diagram for 18 mm Plywood

Max. /	Allowable Spacing of Spacing of Support	=	575 mm (allow.)
Actua	I / Assembly Spacing of Support	=	400 mm < allowable OK





### C. Check Secondary beam

Technical Information { see reference page- )

## Infill beam

length Actual= 1.20 mLength Normal = 1.30 mSafe Distributed load=7.50 kN/ M²

Imposed load		=	9.00 kN/m <sup>3</sup>
Secondary beam (infill Beam) Spacing	=		400 mm

### Loading Calculation

w=iposed load x secondary beam spacing w = 9.00 kN/  $M^2$  x 0.400 = 3.60 kN/ m

Since the actual load is 3.60 kN/ m x 1.20 =4.32 kN < 7.50 kN so it's OK. Therefore, Secondary beam is safe.

### D. Check Primary beam

Technical Information
{ see reference page- )

Decking beam

length Actual= 1.65mLength Normal = 1.80 mSafe Distributed load=40.00 kN/ M²

#### **Loading Calculation**

w=iposed load x primary beam spacing w = 9.00 kN/ M<sup>2</sup>x 1.80x1.30 =21.06 kN/ m

Since the actual load is 21.60 kNwhich is below the allowable load **40kN** <u>Therefore, Primary beam is safe.</u>



#### E. Support System

(Combination of Standard, ledgers, Drop head, Base Jack, Universal Jack & Bracings)

Technical Information According to Cuplock Technical Data Information allowable load per Standard with lift of ledger 1.5m and providing bracing every after 2 bays at both directions is 35 kN

#### **Loading Calculation**

Area of Slab per standard	=	1.80x1.30= 2.34 M <sup>2</sup>
Self weight of Decking	=	0.50 kN/M <sup>2</sup>
Load on per Standard	=	9.00+0.50 *2.34=22.23 kN
	Therefore Support is safe. OK	

#### Ledger Spacing

According to BS 1139-1:1990, see table B.2 reference Maximum permissible axial load for unbraced used tubes with effective length of 1500mm is 35.0 kN is greater than allawable.



## F. Diagonal Bracing

(Diagonal bracing with scaffold tube 48.30 mm Dia. & swivel coupler)

The design of bracing to horizontal resistance force required		
to be transmitted is specifies in BS5975:1996		
Code of practice for falsework		
The BS code specifies minimum lateral stability	y criteria aqualine to	
the greater of either 2.50% of the vertical load	in the standards acting	
horizontal forces from wind erection tolerance	es, non vertical and concrete	
pressure of other forces acting as described in the code.		
<ol> <li>Horizontal force equavalent to 2.50% of vertical loa (Hv)</li> </ol>	= 32.50kN x 2.50% = 0.73 kN/m	
<ol> <li>Horizontal force resulting from erection tolerances 1.0% of applied vertical load</li> <li>H, is 1&amp; of 29.16kN</li> </ol>	= 32.50kN x1.0% = 0.33 kN/m	
Total horizontal force= 0.73+0.33	= 1.06N	
Safe load of diagonal as strut.	= 1.06 / cos35 deg. = 1.26kN	

Use least of A) coupler capacity of 6.30kN

B) Safe load of diagonal as strut.

#### 6.30/1.26=50 say 4 standards, sobracing shall be provided every fourth standard at both direction.

۸.E.