



**DESARCH**<sup>TM</sup>  
**SCAFFOLDING**

# PREQUALIFICATION



**CUPLOCK SCAFFOLDING**  
**SALES, HIRE & ERECTION**



# I N T R O D U C T I O N









The Company was established in the year 2003 and is engaged in the Rental Business of "Cup Lock Scaffolding, Tripod with Aluminium & Tripod with H20 Beams . The Company takes pride in offering the Lowest Rental Charges of Scaffolding in U.A.E Market. This system provides a safe, multipurpose scaffold i.e. easily erected with a minimum of moving parts thus providing efficiency on speed and savings on cost. The decking systems provide a supporting grid for Flat & Hourdi Slab Construction, also facilitating standardized formwork suitable for beam, slab and trough. We also lease out light duty frames, props, scaffold boards & aluminum towers.


The Company offers services for CAD generated Drawings & Designs as per Safe Working Load for all scaffolding needs by Company's skilled qualified professionals and Engineers to the satisfaction of the consultant.



# PREQUALIFICATION DOCUMENT

## Scaffolding Items

-  Base Jack
-  Ledger
-  Standard
-  Universal Jac
-  Drophead
-  Decking Beam
-  Infill Beam
-  Plywood



# CUPLOK Scaffolding System



## CUPLOK – Functional design with simplicity of connection

The CUPLOK system has been designed to meet the requirements of the construction and housing industries.

The success of CUPLOK lies in its principal design features:

- Speed of assembly
- Versatility of application
- Simplicity of components and their connection
- Galvanised components improve corrosion resistance
- Elimination of loose wedges
- No special tools required for assembly (hammer and spirit level only)
- Low maintenance.

## CUPLOK – Easy to erect

No wedges – just a simple locking cup at each node point on the Standards enables connection of the ends of up to four members in one locking action. With all four members attaching at the same level the system is ideal for birdcage construction as well as conventional face scaffolding.

## CUPLOK – Versatile in use

It is suitable for access or formwork support with an extensive range of special applications. The horizontal members can be angled to suit many different applications. The system has been used in triangular, trapezium and is ideal for curved surfaces.

## CUPLOK – Proven design with safety accessories

The CUPLOK system has a proven performance history on an extensive number of sites, meeting the requirements of the various statutory bodies. A comprehensive range of accessories is available to cater for safety requirements such as guardrails, mesh panels, ladder access, stair access and components to provide overhead protection.

## Important

The assembly guidelines contained in this booklet are the recommended methods to be used for CUPLOK products and must be accurately followed to achieve the correct function of the product. Seek advice from the Acrow Formwork & Scaffolding Engineering Department should you need to deviate from the recommendations and technical detail given in this manual.


Use and application of the CUPLOK system must be in accordance with AS1576, AS4576, AS3610, Occupational Health & Safety Regulations of the regulatory authorities and approved industry codes of practice. The illustrations in these assembly instructions are recommended guidelines only.

## Product Codes

The product codes are shown on pages

## Safety Warning

It is recommended that users of the CUPLOK system employ and implement appropriate procedures and control measures to eliminate or control any risk of possible musculoskeletal disorder/injury while manually handling CUPLOK components. Refer to your local regulatory authority for Codes of Practice on manual handling or other approved and recognised guidelines for correct and appropriate manual handling procedures.




## Cup-lock with Steel Decking and Infill System

### Ledgers

All ledgers have identical forged blade ends, with minimum projection to avoid damage.


Other ledger sizes available are

1.3m, 1.2m, 1.0m, 0.9m




### Standards


Maximum leg load capacity : 57kN



SIZE (m)	WT. (kg)
3.0	14.8
2.8	14.0
2.5	12.4
2.3	11.4
2.0	10.0
1.8	9.0
1.5	7.9
1.3	6.5
1.0	5.0
0.8	4.1



# Cup-lock Decking Standard Components



Length (m)	2.5	1.8	1.2
Weight (kg.)	26.4	18.0	11.9


### Decking Beams

Includes 100mm wide top flange, which eliminates the necessity of a plywood infill, whereby maintenance costs are cut down.

### Infill Beams

Used to provide skeletal support for plywood decking

Length (m)	1.7	1.5	1.2	0.9
Weight (kg.)	9.1	8.1	6.5	5.0




**Beam Shoe**

### Dropheads

The quick action supplied by dropheads along with nuts and bolts, is designed to fit on standard props or adaptors for cuplock scaffolding.

Maximum axial load: 40kN



### Socket Base (Adaptor)

It provides a base for the universal jack & also connects universal jack to drophead.

### Intermediate Transoms




Length (m)	1.3	1.8	2.5
Weight (kg.)	5.5	7.3	9.5




**BASE JACK**



**UNIVERSAL JACK**



**U-HEAD**  
150x170x5.8







**CONNECTING PIN**





**BOLT & NUT**

# Adjustable Jacks Sizes









Thickness = 5 mm

Thickness = 5 mm






# Slab Formwork




Locate the blade end of Horizontals into lower cup.



Lower the upper cup down the vertical and rotate




Tighten with a hammer blow



A positive & rigid connection of four units is achieved in one single action

### CUP Lock Decking System offers a Choice of 12 Supporting Grids






Supporting grids A 1.8m x 1.8m B 1.8m x 1.6m					Supporting grids G 1.8m x 1.0m H 1.2m x 1.0m				
Supporting grids C 1.8m x 1.3m D 1.2m x 1.8m					Supporting grids J 2.5m x 1.8m K 2.5m x 1.6m				
Supporting grids E 1.2m x 1.6m F 1.2m x 1.3m					Supporting grids L 2.5m x 1.3m M 2.5m x 1.0m				
Grid (mxm)	Slab Thickness (mm)	In Fill Centres	Grid Area (m)	Leg Load (kN)	Grids (mxm)	Slab Thickness (mm)	In Fill Centres	Grid Area (m)	Leg Load (kN)
Type A Infill Beam 1.7m Beams 1.8m Long	100	610	3.24	14.4	Type G Infill Beam 0.9m Beams 1.8m Long	300	610	1.8	16.6
	150	610		18.4		400	610		21.2
	160	610		19.2		500	488		25.7
	200	488		22.4		600	488		30.0
	250	488		26.3		700	406		34.5
	280	488	28.7		800	406	38.9		
Type B Infill Beam 1.5m Beams 1.8m Long	200	610	2.88	19.9	Type H Infill Beam 0.9m Beams 1.2m Long	600	488	1.2	20.4
	250	610		23.4		700	488		23.0
	300	488		26.9		800	406		25.9
	350	488		30.5		900	406		28.9
	400	406		34.0		1000	348		31.8
	440	406	36.8		1250	348	39.1		
Type C Infill Beam 1.2m Beams 1.8m Long	350	488	2.34	24.75	Type J Infill Beam 1.7m Beams 2.5m Long	150	610	4.50	25.5
	400	488		27.6		160	610		26.6
	450	406		30.5		175	610		28.3
	500	406		33.3		200	488		31.0
	550	348		36.2		225	488		33.8
	600	348	39.1		355	488	37.1		
Type D Infill Beams 1.7m Beams 1.2m long	100	610	2.16	10.1	Type K Infill Beam 1.5m Beams 2.5m Long	150	610	4.00	22.7
	125	610		11.5		200	610		27.6
	150	610		12.9		250	610		32.5
	200	488		13.7		275	610		35.0
	250	488		18.5		300	488		37.4
	280	488	20.2		320	488	40.0		
Type E Infill Beam 1.7m Beams 1.2m long	200	610	1.92	13.2	Type L Infill Beam 1.2m Beams 2.5m Long	150	610	3.25	18.4
	250	610		15.6		200	610		27.4
	300	488		18.0		300	610		26.4
	350	488		20.3		350	488		30.4
	400	406		22.7		112	488		35.4
	440	406	24.5		488	40.0			
Type F Infill Beams 1.2m Beams 1.2m long	400	488	1.56	18.4	Type M Infill Beam 0.9m Beams 2.5m Long	200	610	2.5	17.3
	450	488		20.3		300	610		23.4
	500	488		22.2		400	488		29.5
	600	488		26.0		450	488		32.6
	660	406		28.3		500	488		36.6
	730	406	31.0		560	488	40.0		

The above figures are based on the maximum load carrying capacity of the infills, Decking Beams and 40kN capacity of Cup-lock drophead. Leg load calculations are based on concrete density of 24.3kN/m<sup>3</sup> and super-imposed loads of 2kN/m<sup>2</sup> including the weight of the formwork.

# Cup-Lock Component Loadings

## Permissible Loads on Horizontal Components

Permissible loads on the various components are shown in the diagram



## CUP LOCK SUPPORT GUIDE

For standards at the beginning and end of a row, the loading figures for the top and base lifts have to be reduced by 5%, except if jack bracing is used. This also applies to the use of Cup-lock in towers and single bays. At least two lacing levels have to be used on each vertical. When calculating horizontal forces, include for wind forces, the effect of eccentricity, and out of plumb (in accordance with British Standard 5975).

Take care that structure is stable in the unloaded condition, especially if towers or narrow structures are used. All standards should be erected plumb. Horizontal forces should be distributed over all verticals as evenly as possible. Sound footings should be provided to prevent settlement of the standards.

## Permissible Loads on Base Components

### Vertical Axial Load up to 57kN

The loadings will vary according to the horizontal loads taken into account and the actual extension of the Jack required.



86 cm Universal Jack

### Permissible loads on standards (In false work structures only)

The tables below show the permissible loads per vertical for falsework structures incorporating suitable bracing. The values apply regardless of the type of formwork supported.

However, permissible loads can be influenced by a number of factors. If any doubt, reference should be made to the EXTRA CO Design Office.


### Internal Verticals

Lift	Vertical Load (kN)	
	1.8m Bay	2.5m Bays
1.0	57.0	57.0
1.5	55.0	54.0
2.0	40.0	36.0
2.5	26.0	25.0

### External Verticals

Lift (m)	Bay length (mm)				
	600	900	1200	1800	2500
1.0	57.0	57.0	57.0	57.0	57.0
1.5	55.5	54.5	53.5	52.0	51.0
2.0	38.0	36.0	34.5	34.0	32.0

## Explanation



### The technique of early striking

Early striking is a technique whereby the formwork is removed 3 to 4 days after pouring a slab, but the supporting structure of scaffolding or props remains undisturbed until the concrete is strong enough to support its own weight over its full span.


Concrete generally takes 28 days to attain its full constructional design strength. Most engineers will only permit the complete support to be removed after about 10 to 14 days, depending on the ambient temperature and cube strength tests.

With today's high costs of formwork, it is important to use it as frequently as possible. Traditional formwork locked in situation for 10 to 14 days with a pouring cycle in excess of this is outmoded by the Cup-lock early striking system and its facility to speed the cycle of operations. This practice has been widely accepted especially as the rising costs of materials and labour have proved that the early striking is safe, efficient and cost-effective.

### How it is set

A complete set of cup lock decking and support is used for the 1<sup>st</sup> floor slab. Three to four days after pouring the concrete, the infills and decking beams may be struck for re-use on the 2<sup>nd</sup> floor slab while the support remains in place during the rest of the curing period. In practice it is found that supports around columns and close to walls & beams can be removed and this amounts to about 1/3 that are free for re-use. Therefore an approximate additional 2/3 of support will be required for the 2<sup>nd</sup> floor. Three to four days after pouring concrete on the 2<sup>nd</sup> floor, the formwork may be removed.

### Traditional formwork



Based on 7day cycle, it can be seen how Cup-lock deckings increase output whilst employing less labour more effectively as it is used during curing periods.

Therefore less Cup-lock deckings can be used to achieve the same output as traditional methods

# Adjustabe Jacks Inspection & Load Capacities



Test Conducted: With reference to ANSI/SSFI BC100-505 Standards for testing and rating scaffold assemblies and components and client's requirements.

**Test Results:**

Manufacturer: /		Model # / Product Identification /	
Test Date: 2016.7.15	Test # : 1.2	Test Location: SGS OCM Lab	Factor of Safety (FS) /
Reading			
Sample No.	Ultimate Vertical Load	Failure Mode	
Test 1	155.0kN	The screw rod was bent and cracked	
Test 2	145.0 kN	The screw rod was bent	

Note: The maximum height from the bottom of the screw rod to the top surface of the handle nut is 200mm as per client's requirement.

Statement: Unless otherwise stated the results shown in this test report refer only to the sample(s) tested.


**Test Photos:**




Before test

In test

After test





Cup-lock combined with aluminum beam forms strong, lightweight, economical system. It also reduces waste and site labour costs



### G 6 BEAM



BENDING MOMENT EXCEEDS 6 kNM  
SIZE 150 x 80MM  
WEIGHT ONLY 3.162 Kg/m  
STANDARD LENGTHS UPTO 7 METRES


### G 12 BEAM



BENDING MOMENT EXCEEDS 12 kNM  
SIZE 165 x 95MM  
WEIGHT ONLY 4.750 Kg/m


(DESIGNED AND PRODUCED IN GCC)

## CUPLOCK APPLICATION





- ◇ Cup-lock Scaffolding is a temporary structure used to support a slab, work crew and materials to aid in the construction, maintenance and repair of buildings, bridges and all other manmade structures.
- ◇ Cup-lock is a fully galvanized or painted multi-purpose steel scaffold system suitable for providing general access and supporting vertical loads.
- ◇ All vertical standards and ledgers tubes are 48.3mm diameter with 3.00 or 3.20 mm thickness.
- ◇ Cup-lock is the world's most widely used system scaffold.
- ◇ Cup-lock's key feature is its unique circular node point which allows up to 4 horizontals to be connected to a vertical in a single fastening action-making it probably the fastest and safest system available.


- ◇ The ease of handling, easy storage space requirements and high load bearing capacity are the main reasons for its immense popularity.
- ◇ The comprehensive range of Cup-lock components allows it to be used with traditional scaffold boards or battens. It can be used to create a huge range of access and support structures, circular scaffolds, loading towers etc.
- ◇ Cup-lock Scaffolding is a multi-purpose system suitable for access and support in all types of construction of building & Civil engineering project.



**Cuplock Falsework to support and shuttering the concrete slabs  
At different heights and levels**








Cup-lock versatility and wide range of accessories make it an ideal system for almost any situation, from simple domestic building projects to the most complex access and support structures. Its ability to follow curve and complex profiles make it equally suitable for mainly industrial maintenance situations.

## Support Structures

- ◇ Cup-lock is widely used to create falsework support structures.
- ◇ Its high leg load capacity and range of components gives the system capability to tackle virtually any support application.
- ◇ For formwork support a wide range of grid variations can be created to suit the loading requirements.
- ◇ The key advantage of Cup-lock of support structure is its unique node point (i.e., four connections in one action).
- ◇ Cup-lock scaffolding is lighter than traditional scaffolding.



## Cuplock Staircase and Planks





## Access Towers



- ◇ Square or rectangular access towers can be erected with standard Cup-lock components using either jacks and base plates
- ◇ The working platform can be formed using either scaffold boards or battens.
- ◇ All Access Scaffolds must comply with the general requirements of the Construction (Health, Safety & Welfare) Regulations 1996 & Code of Practice BS5973.
- ◇ BaiLi Cup-lock system meet the requirements of the international standard for health and safety Cup-lock constructs and maintains an installation that can seriously affect the life acceptance and efficiency of the finished installation.


Cup-lock Scaffolding System is suitable for support structures applications through the following:

1. High standard load capacity.
2. Range of components that give the system capability to tackle virtually any support application.
3. Formwork supports wide range grid variations that can be created to suit the loading requirements and any structures types and heights.

## Characteristics



# Cuplock SUPPORTING FLOOR SLABS



# LIST OF MAJOR CLIENTS / CONSULTANTS



NO	COMPANY NAME	CONSULTANT	PROJECT
1	SALEH CONSTRUCTION LLC	M/S LACASA	PROPOSED G+3P+19 STOREY RESIDENTIAL BUILDING ON PLOT NO JVC 12NHR 003 @ AL BARSHA SOUTH 4TH -681 DUBIA UAE
2	GLOBAL CONTRACTING LLC	BARAJEEL ENGINEERING CONSULTANTS	PROPOSED B+G+M+4P+GYM+23TYP+ROOF ON PLOT NO 345-430 AT DOWNTOWN DUBAI
3	TRANSEMRIRATES CONTRACTING LLC	ALAJMI CONSULTANT ENGINEERING	PROPOSED 2B+G+3P+28+R COMMERIAL AND RESIDENTIAL BUILDING ON DM PLOT NO SP-B-025 @ TECOM INVESTMENT FZ-LLC (DUBIA SCIENCE PARK)
4	AL HIKMA BUILDING CONTRACTING LLC	ARCHEN ENGINEERING	PROPOSED G+3P+12 FLOOR RESIDENTIAL BUILDING ON PLOT NO 373-4532 AL BARSHA , DUBAI, UAE
5	ALI MOOSA & SONS CONTRACTING	NATIONAL ENGINEERING CONSULTANTS	MIXED USE BUILDING 4B+G+H.C+MECH+L+40 FLOOR (RESIDENTIAL)+ROOF PLOT NO 3930975, JLT, DUBAI UAE
6	UNION CONTRACTING LLC FOURTH PLOT NO JVC15BMRH010	BEL-YOAHAH	RESIDENTIAL &COMMERCIAL BUILDING G+4P+18TYP @ AL BARSHA SOUTH
7	SBCC SQUARE GENERAL CONTRACTING CO LLC	ARCHITECTURAL CORNER CONSULTANTS	26+G+M+10 FLOOR KHALDIA HOTEL @ PLOT NO 1246578 LOCATION MURAOQBAT DUBAI
8	DONE CONTRACTING LLC	JOUZY ANANTA	G+2P+10 AL FURJAN 4 LOCATION AL FURJAN DUBAI
9	PARK WAY INTERNATIONAL CONTRACTING LLC	DOME CONSULTING ENGINEERS	G+3P+9+ROOF FLOOR COMMERCIAL BUILDING PLOT NO JV1C10M1M001 LOCATION AL BARSHA SOUTH FORTH 681
10	AL TAYER STOCKS L.L.C	DESIGN AND ARCHITECTURAL BUREAU	NEW COMMERCIAL & RESIDENTIAL B
11	ARIFCO BUILDING CONTRACTING	BHNS ENGINEERING CONSULTANTS	80-JEBEL ALI
12	ASHYANA CONTRACTING L.L.C.	ARCH GROUP CONSULTANTS	SHARJAH IND. 17
13	CITY NIGHTS CONTRACTING LLC	GOLDEN SQUARE ENGINEERING CONSULTANTS	82-G+4 LAB.ACCOM
14	GLOBAL GREEN BRIDGE CONT.L.L.C	AL KHAWAJAH ENGINEERING CONSULTANTS	G+4 LABOUR ACCOMODATION AT JEBEL ALI
15	SALEH CONSTRUCTION	DESIGN CENTER	B+G+M+2+HIC RESIDENTIAL BLDG. AT AL KARAMA DUBAI
16	GOLDEN WING CONTRACTING.	NEXT ENGINEERING CONSULTANTS	GROUND+MEZZ.+2TYP FLOOR COMMERCIAL+OFFICE & RESIDENTIAL BLDG. AL KHABAISIS, DUBAI.
17	CHICAGO MAINT. & CONST.CO. LLC	GAJ ARCHITECTURAL & CIVIL ENG	GEMS INTERNATIONAL (G+2) SCHOOL, AL KHAIL DUBAI
18	AL HIKMA BUILDING CONTRACTING	AL ABDOOLI ENGINEERING CONSULTANTS	ISLAMIC AFFAIRS-MOSQUE(JUMMA) QURAN SCHOOL WADI ALAMADI, U.A.E
19	ROTANA CONTRACTING	ROKN AL HANDASA CONSULTING ENGG	GROUND+6 BUILDING AL WARQA'S FIRST
20	AROMA INTERNATIONAL	ARC INTERNATIONAL ENGINEERING CONSULTANTS	PROP BIRDS MARKET COMPLEX AT WARSAN THIRD, DUBAI.
21	TRIPLANET INTERNATIONAL FZC	BARAJEEL ENGINEERING CONSULTANTS	7 RESIDENTIAL BUILDINGS IN SPORTS CITY DUBAI
22	UNION CONTRACTING	TEO A. KHING DESIGN CONSULTANTS SDN BHD, (DUBAI)	DEVELOPMENT AND CONSTRUCTION OF THE MEYDAN BUSINESS PARK
23	AL BWARDI ENGINEERING	PARADISE HOME ENGINEERING	GRD FLOOR+ROOF SERVICES SHOPPING MALL AT UMM AL SHEIF
24	LARSEN & TOURBO LIMITED	TRANSCO	132/33KV SUBSTATION AT SUDHA PORT IN FUJAIRAH
25	BELHASA ENGINEERING & CONTRACTING CO. LLC	HOLFORD ASSOCIATES	3B+G+M+3 UPPER COMMERCIAL & OFFICE BUILDING
26	AMANA STEEL & BUILDING CONSTRUCTIONS	OBE CONSULTANT	DP WORLD
27	IDEAL SYSTEM CONSTRUCTION	ELITE ENGINEERING CONSULTANTS	HOTEL (2B+G+3+PENTHOUSE ) HOR AL ANZ
28	MS LOOTAH CONSTRUCTION	RENDERES ENGINEERING	B+G+4 ROOF BUILDING @AL WARQA
29	ARMADA CONTRACTING LLC	MODEL ENGINEERING CONSULTANTS	PROPOSED G+M GROUP OF 61 WAREHOUSE UNITS+ OFFICE ON PLOT NO IMPZ.C.47 AT MEAISEM FIRST DUBAI PRODUCTION CITY, DUBIA , UAE
30	SPAN STEEL CONSTRUCTION LLC	WINNER HOLISTIC CONSULTANT	PROPOSED G+M+10 OFFICE & WAREHOUSE ON PLOT NO TP030507 TECONO PARK , DUBIA , UAE
31	ADNAN CONTRACTING LLC	DESIGN CENTER	PROPOSED 3B+G+P+15 RESIDENTIAL BUILDING PLOT NO - AFMU029B AT JABAL ALI FIRST, MORANO -3 AND PLOT NO AFMU029A AT JABAL ALI FIRST, MORANO -2
32	TAV INVESTMENT CONSTRUCTION & OPERATIONS		AL MAKTAB AL ASRI ENGINEERING CONSULTANT SULFA TOWER 4B+G+4P+66 TYPICAL+2S+2PH+1HC RESIDENTIAL TOWER MARSIA DUBAI
33	FAMILY STAR CONSTRUCTION LLC	WINNER CONSULTANTS & ENGG.	LABOUR ACCOMODATION AT JEBEL ALI

# Test Certificates & Alum Profile

**Independent Soil Testing Laboratories LLC** **مختبرات التربة المستقلة**

**REPORT ON LOAD TEST OF SCAFFOLDING PROPS FOR FALSEWORK EQUIPMENT**  
(BS 5507 Part 3, 1992)

**Client:** Alhady Building Contracting LLC **Sample Reference No.:** NP  
**Address:** P.O. Box 92288 Abu Dhabi, UAE **Date of sampling:** NP  
**City:** UAE **Number of Reference No.:** NP  
**Contract:** NP **Lot No.:** NP  
**Project Name:** NP **Sampling location:** NP  
**Proposed No.:** NP **Date Sample Received:** 02/02/2019  
**Size of Sample:** 3 m **Condition of sample at received:** Good  
**Sample Name:** Submarine Scaffolding Props (Vertical Support) **Sample brought in by:** Client  
**Sample Description:** Submarine Scaffolding Props (Vertical Support) **Sampled by:** Client  
**Marking on Sample:** Doha (State DE) Tash338 **Report Date:** 05/10/2019  
**Name of sample:** Doha scaffolding **Standard length of sample:** 3.3 meters  
**Report No.:** ST18-090229 **SA 51** **Date test started:** 05/10/2019  
**Site Project No.:** ST18-0249 **Date test completed:** 05/10/2019  
**Sample No.:** ST18-090229 **Tested by:** MS

**TEST RESULTS:**  
Clear diameter of lower pin: 77.3 mm  
Clear diameter of lower eye: 89.3 mm  
Clear pinless length of sample when loaded: 5.2 meters  
Type of testing: Maximum Load or Failure

Specimen No.	*Peak Load (kN)	Observation
ST18-090229-1	275	Failure on hole end observed

**Independent Soil Testing Laboratories LLC**  
Manama St-12, Plot No-02, PO Box 148961, Abu Dhabi, U.A.E.  
Tel: +971 2 5532102, Fax: +971 2 5532103  
Email: info@desarch.com, Website: www.dsc.ae

**CONCRETE THICKNESS - 300 MM, 350 MM, 400 MM, 450 MM, 500 MM, 550 MM, 600 MM**  
Alan Dulka - 3.164 (per) DE-100-01

Max = 343.7mm  
Min = 206.25mm  
Mean = 274.975mm

**Table 1: GE-1049 Profile Performance**

Concrete Thickness (mm)	200	300	400	500	600	700	800	900	1000	1100	1200	1300	1400	1500	1600	1700	1800	1900	2000	
200mm	2137	2029	1901	1806	1826	1772	1725	1661	1603	1572	1524	1484	1449	1419	1390	1361	1332	1303	1274	1245
300mm	1987	1888	1801	1743	1684	1645	1583	1527	1473	1429	1385	1341	1307	1273	1239	1205	1171	1137	1103	1069
400mm	1868	1776	1721	1677	1629	1588	1547	1507	1467	1427	1387	1347	1307	1267	1227	1187	1147	1107	1067	1027
500mm	1801	1726	1671	1632	1592	1551	1511	1471	1431	1391	1351	1311	1271	1231	1191	1151	1111	1071	1031	991
600mm	1743	1677	1638	1602	1562	1522	1482	1442	1402	1362	1322	1282	1242	1202	1162	1122	1082	1042	1002	962
800mm	1677	1619	1580	1543	1502	1462	1422	1382	1342	1302	1262	1222	1182	1142	1102	1062	1022	982	942	902
Low	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180	2180

**AL HOTAI - STANGER LABORATORIES** **مختبرات الحوتاي ستانجر**

**TEST REPORT**

**LOAD TEST ON CUPLOCK STANDARD**

Report date : 29.08.17

Report number	D17 - 276437-1	Source / Suppliers	Not given
Project name	Quality Assurance	Sample location	Site stock
Client ref./request no.	Not given	Sampled by	Client
Sample description as identified by client	Cuplock Standard (D800)	Sampling date/time	Not given
Source / Local Supplier	Not given	Sampling method	Not given
Sampled by	Client	Client ref./request no.	Not given
Date/time sample received	22.08.17 12:00 Hrs.	Sample delivered by	Client
Date tested	28.08.17	Date/time sample received	17.11.17 11:20 Hrs.
Tested by, name/location	AMS / DXB	Tested by, name/location	JMR, DXB

**Results:**

Peak load, (kN)	Observation
44.8	Buckling of standard

Remarks : None  
This report relates only to the sample tested and shall only be reproduced in full and with the written approval of AHS Laboratories

Joseph Mathers  
Head of Physical/Mechanical Dept.

Dr. Mathers, Khatib Al-Hotai Stanger Laboratories Manager  
For Al HotaI-Stanger Laboratories

**AL HOTAI - STANGER LABORATORIES** **مختبرات الحوتاي ستانجر**

**TEST REPORT**

**LOAD TEST ON BASE JACK & U-HEAD**

Report date : 28.11.17

Report number	D17 - 284648-1	Source / Suppliers	Not given
Project name	Quality Assurance	Sample location	Site stock
Client ref./request no.	Not given	Sampled by	Client
Sample description as identified by client	Base Jack (480mm open) & U-Head (480mm open)	Sampling date/time	Not given
Source / Local Supplier	Not given	Sampling method	Not given
Sampled by	Client	Client ref./request no.	Not given
Date/time sample received	17.11.17	Date/time sample received	17.11.17 11:20 Hrs.
Date tested	28.11.17	Tested by, name/location	JMR, DXB

**Test method :** As shown in the photograph

**Results:**

Applied load (kN)	Failure of base jack & u-head
104.3	

Remarks : None  
This report relates only to the sample tested and shall only be reproduced in full and with the written approval of AHS Laboratories

Joseph Mathers  
Head of Physical/Mechanical Dept.

Dr. Mathers, Khatib Al-Hotai Stanger Laboratories Manager  
For Al HotaI-Stanger Laboratories

**DESARCH**  
SCAFFOLDING

مستشارتي استشارات استشارات  
Desarch Building Contracting L.L.C

**RE-PROPPING CALCULATION FOR TYPICAL FLOOR SLAB**  
Client : **Mrs. AL TAYER REALSTATE COMPANY**  
Project : **PROPOSED B+G+4 FLOORS COMM & RES. BUILDING ON PLOT NO. 818397 AT NADD AL SHEBA TAD, DUBAI**

Slab thickness = 270mm Area = 7092 sqm  
Cycle time = 15 days Clear Height = 8.2m MAX.

**Load from the fresh slab (1st Floor)**  
Dead Load of fresh slab = 0.27 x 25 kN/m<sup>3</sup> = 6.75 kN/m<sup>2</sup>  
Formwork Load = 0.50 kN/m<sup>2</sup>  
Construction Live Load on formwork = 1.50 kN/m<sup>2</sup>  
Total Load from fresh slab = 8.75 kN/m<sup>2</sup>

**Load acting on bottom Slab - 1 (Ground Floor)**  
Load from fresh slab = 8.75 kN/m<sup>2</sup>  
Self Weight of bottom Slab-1 = 0.3 x 25 kN/m<sup>3</sup> = 7.50 kN/m<sup>2</sup>  
Total load acting of bottom Slab-1 = 16.25 kN/m<sup>2</sup>  
Less strength achieved by slab-1 after 15 days is 98.3 % (refer Table-B)  
(For designed load of slab refer Table-A below)  
Total Load to be Transferred to bottom Slab-2 = 4.75 kN/m<sup>2</sup>

**Re-Proping to be provided for SLAB-1 as Calculated below**

Capacity of prop = 20 kN  
Required Spacing of Props = 20 / 4.7 = 2.00m

**Table-A - DESIGN LOAD OF SLAB ASSUMED**  
Self weight of slab = 0.27 x 25 kN/m<sup>3</sup> = 6.75 kN/m<sup>2</sup>  
Live load = 5.00 kN/m<sup>2</sup>  
Floor finish = 0.50 kN/m<sup>2</sup>  
Partition load = 1.00 kN/m<sup>2</sup>  
Total Designed load = 13.25 kN/m<sup>2</sup>

**Table-B - STRENGTH OF CONCRETE ASSUMED**  
Basic Data: 28 days = 98%, 7 days = 97%, 14 days = 98%, & 21 days = 100%  
After 15 days 98.3% = 0.983 x 11.75 = 11.55 kN/m<sup>2</sup>  
More than 21 days 100.0% = 1 x 11.75 = 11.75 kN/m<sup>2</sup>  
More than 21 days 100.0% = 1 x 11.75 = 11.75 kN/m<sup>2</sup>  
More than 21 days 100.0% = 1 x 11.75 = 11.75 kN/m<sup>2</sup>

Color Coding: **GREEN** - Lowest Design Load **YELLOW** - Medium Design Load **RED** - Highest Design Load

DESARCH BUILDING CONTRACTING L.L.C  
P.O. Box 17887, Dubai - UAE Tel: 04 3337076 Fax: 04 3337076  
P.O. Box 32888, Abu Dhabi - UAE Tel: 02 6506000 Fax: 02 6506001  
E-Mail: info@desarchbuilding.com  
www.desarchbuilding.com

**DESARCH**  
SCAFFOLDING

**LACASA**  
Architects & Engineering Consultants

Project: Proposed G+3P+19 Storey Residential Building - On Plot No. JVC12NHR8003 at Jumeirah Village Circle, Al Barsha South Fourth-581, Dubai - UAE

**SHOPDRAWING SUBMITTAL**  
Date: 12/12/2018 Reference: SCDFW12018000000

Submitted: Shop Drawing Submittal for Scaffolding Layout of First Postum Slab & Typical Floor Slab.

Approval Status:  
1 Scaffolding Layout of First Postum Slab:  Approved  Shop drawing attached  
2 Scaffolding Layout of Typical Floor Slab:  Approved  Shop drawing attached

Shopdrawing set must be available for transmittal containing: shop drawing, shopdrawing & shopdrawing approved for execution must be sealed and signed by the designer.

Category:  Structural  Architectural  Mechanical  Electrical  
 Others  Safety

The Contractor's Representative: *[Signature]* Date: 12-12-2017

**DESIGNER'S COMMENTS:**  
- Conditions not suitable for scaffolding erection.  
- Final party must be handled by Architectural & Mechanical.  
- Refer to the site condition about level of ground.  
- Shop drawing not limited.  
- Refer to the site condition about beams of slab.

APPROVED:  APPROVED AS NOTED:  REVISION:  RETYPED:  NOT APPROVED:

For The Employer: *[Signature]* Date: 13 FEB 2017

**DESARCH**  
SCAFFOLDING

مستشارتي استشارات استشارات  
Desarch Building Contracting L.L.C

To: **Mrs. CITY DIAMOND CONTRACTING**  
P.O.Box-37927 Dubai, U.A.E.  
Tel: 04 3309000 Fax: 04 3309001

Date: 04 - 03 - 2017

Dear Sir,

In compliance with your request the undersigned inspected the scaffolding supports for Mezzanine Floor Slab.

**SCAFFOLDING INSPECTION REPORT**

Consultant : Mrs. ARCHCORP Architectural engineering  
Client : UNITRA METS DUBAI, UAE  
Contractor : Mrs. CITY DIAMOND CONTRACTING.  
Project : UNITRA METS LOGISTICS & WAREHOUSING FACILITY USM RAMBOOL, DUBAI, UAE  
Area : MEZZANINE FLOOR SLAB.  
Scaffold Type : Cup Lock Type (D LOCK)  
Designed by : Mrs. DESARCH BUILDING CONTRACTING L.L.C. (SCAFFOLDING DIVISION)  
Erected By : Mrs. CITY DIAMOND CONTRACTING.  
Scaffolding Supplier : Mrs. DESARCH BUILDING CONTRACTING L.L.C. (SCAFFOLDING DIVISION)

Post erection inspection is performed and found in accordance of Shop drawings by Mrs Desarch Building Contracting L.L.C (Scaffolding Division).

Scaffolding Erection is found Erected as per drawing approved by you and Found ok for Pouring.

For Desarch Building Contracting L.L.C. *[Signature]*

DESARCH BUILDING CONTRACTING L.L.C  
P.O. Box 17887, Dubai - UAE Tel: 04 3337076 Fax: 04 3337076  
P.O. Box 32888, Abu Dhabi - UAE Tel: 02 6506000 Fax: 02 6506001  
E-Mail: info@desarchbuilding.com  
www.desarchbuilding.com

**lacoce**  
architects & engineers  
3rd Floor, Jumeirah Village Circle, Dubai - UAE  
Tel: 04 3337076 Fax: 04 3337076

**CLIENT** MAHD AL FUTAIM  
**CONSULTANT** lacoce architects & engineers  
**CONTRACTOR** Mrs. City Diamond Contracting

**SUBMITTAL COVER SHEET**

TRIAL AL QHAF SHOW VILLAS & SALES PAVILION  
Project No: 10000000000000000000  
Client: MAHD AL FUTAIM  
Consultant: lacoce architects & engineers  
Contractor: Mrs. City Diamond Contracting



Submission No: AT/GHAF/S3025/SD/STR-067  
Revision No: 1  
Date: 04-03-2017  
Shop Drawing: AT/GHAF/S3025/SD/STR-067

DESIGN REVIEW STATUS:  
 A - Approved  
 B - Approved with Comments  
 C - To Be Re-submitted  
 D - Rejected

DESIGN CONSULTANT'S COMMENTS:  
- Contractor to verify slab limits according to approved shop drawings.  
- Approval of Desarch to be submitted for Engineer's review and approval.

DESIGN CONSULTANT'S SIGNATURE: *[Signature]* Date: 3.03.2017

PROJECT MANAGER'S APPROVAL: *[Signature]* Date:   
For and on behalf of Project Manager:   
Date:   
Distribution: Original to Al Tayer Blocks  
Copies to: Subcontractors

 <p>سي انش سي لمقاولات البناء ش.ذ.م.م. CHC Building Contracting L.L.C</p>	<p>PROPOSED RESIDENTIAL BUILDING (B+G+4) For: KHALED AHMED QASSEM AL KHATIB (NAFFCO) Plot No. (681-1011) @ Al Barsha South 4th, Dubai, U.A.E.</p>	 <p>أرت للاستشارات استشاريون في العمارة والهندسة ART CONSULTANTS CONSULTING ARCHITECTS &amp; ENGINEERS</p>
--	---	--

ART-2015-05

SHOP DRAWINGS SUBMITTAL	REF No. SD-12 / J-170	REV No.
-------------------------	-----------------------	---------

Discipline:  Civil/Structural  Architectural  Electrical  
 Mechanical  Plumbing  Others

To: M/s. ART Consultants:  
Please find attached the following shop drawings for your approval/comments:

S. #	Drawing No.	Rev.	Title	Remarks
1	DBC/B2018/2120		WATER TANK & PUMP ROOM SLAB SCAFFOLDING LAYOUT	

We hereby confirm that the undersigned have reviewed the drawings.



<p>CHC Building Contracting LLC</p> <p>Submitted By:</p>	 <p>Signature &amp; Stamp:</p>	<p>Approval required by:</p> <p>18-Feb-18 Date:</p>
--	---	---


**ART CONSULTANTS COMMENTS:**

Approved  
 Approved with Comments  
 Not Approved, Resubmit

**Comments:**

- Scaffolding is solely main contractor responsibility.
- Submit prequalification of the scaffolding contractor for engineer approval.
- Scaffolding shall be fixed by certified labor & certified by the safety engineer.
- Submit scaffolding safety certificate prior to pour the concrete.

Checked by:  Time: 1:54 By:  Date: 20/2/2018

Stamp & Signature:  Date: 20/2/2018

Note: ART Comments shall not be considered as a reason of claim of any type unless it is issued via E.I. The contractor should seek an E.I. if he considers that ART comments contains financial or time impact.



<b>CLIENT</b> MAJID AL FUTTAIM	<b>CONSULTANT</b> Iacoco architects & engineers	<b>CONTRACTOR</b> AL YAFER BUILDING LLC
<b>SUBMITTAL COVER SHEET</b>		
<b>TRIAL AL GHAF SHOW VILLAS &amp; SALES PAVILION</b>		
Project No: 0002	Revision No: 8	AT/SNHAF/53025/SQ/STR001
Client: Majid Al Futtaim Trial Al Ghaf Phase A L.L.C	Revision Date:	Page 18
Contractor: Al Yafar Building LLC	Title:	Shop Drawing: 5-4-2018
<input type="checkbox"/> NEW SUBMITTAL OF THIS TYPE <input type="checkbox"/> OR RE-SUBMITTAL		
<input type="checkbox"/> Shop Drawings & Schedules <input type="checkbox"/> Method Statements <input type="checkbox"/> Preliminary As-Built Drawings <input type="checkbox"/> Samples <input type="checkbox"/> Progressions <input type="checkbox"/> As-Built Drawings <input type="checkbox"/> Material & Product Data <input type="checkbox"/> Make-up & GC panel <input type="checkbox"/> O & M Manuals <input type="checkbox"/> Certification & Verification of Submittals <input type="checkbox"/> Inspection & Test Reports <input type="checkbox"/> Other		
<b>DESCRIPTION</b>		
4 Bed Bungalow False Work Drawing		
DESARCH SCAFFOLDING		
PLOT No: YD.A01.002-4 Bed Bungalow		
<b>DESIGN CONSULTANT'S COMMENTS</b>		
<p>ALL levels were checked with approved architectural drawing &amp; clear heights and bottom slab levels to be coincided with MEP services</p>		
<b>CONTRACTOR'S REVIEW</b>		
<input type="checkbox"/> A Approved <input type="checkbox"/> B Approved with Comments <input type="checkbox"/> C To be Resubmit <input type="checkbox"/> D Rejected		
Signature: <i>[Signature]</i> Date: 12-4-2018		
<b>PROJECT MANAGER'S APPROVAL</b>		
Signature: <i>[Signature]</i> Date:		

<b>ALAJMI</b>		Client: Majid Sultan Saoud Sultan Saoud Al (L.L.C)	<b>DESARCH SCAFFOLDING</b>			
<b>SHOP DRAWING SUBMITTAL</b>						
Project: (B+C) 1741042 Proposed Residential & Commercial Building at Nasaif Al Fattan Dubai						
Client: Sheikh Sultan Saoud Sultan Saoud Al (Dubai)		Subj. No: P114/TC/000101/01				
Consultant: AL AJMI ENGINEERING CONSULTANTS		Form. No: P114/TC/000101/00				
Contractor: Transmitters Contracting LLC		Date: 2 Jun 17				
Type: <input type="checkbox"/> Civil <input type="checkbox"/> Architectural <input type="checkbox"/> Electrical <input type="checkbox"/> Lift	<input type="checkbox"/> Survey <input type="checkbox"/> Planning & Drainage <input type="checkbox"/> HVAC <input type="checkbox"/> Other					
S. N.	Shop Drawing No.	Rev.	Date	Draw Title	Contract Draw No.	No. of copies (Hand/Soft)
1	M/55/2/01/001	1	30-11-2016	Partisan Floor Slab With Range Form work		2/Soft 1
<b>Attachments:</b>						
<input type="checkbox"/> Construction requirements We confirm that the attached shop drawings comply with Contract documents <input type="checkbox"/> Yes <input type="checkbox"/> No <input type="checkbox"/> If not, state reasons:						
Submitted by Contractor:		Signature & Stamp:		Received by Engineer:		Signature & Stamp:
Name: Mohamed Alshaban		Date: 02-01-2018		Name: [Signature]		Date: 02 JAN 2018
Title: Project Manager		Date: 02-01-2018		Title: [Signature]		Date: 02 JAN 2018
<b>Chief MEP Engineer's Instructions and Comments:</b>						
<p>Teamwork and safety is main Contractor responsibility          Work to be inspected and approved by 2nd party</p>						
Area Manager's Comments:						
<input type="checkbox"/> Approved <input type="checkbox"/> Approved as noted <input type="checkbox"/> Rejected <input type="checkbox"/> Rejected						
Area Manager:		Signature & Stamp:		Received by Contractor:		Signature & Stamp:
Name: [Signature]		Date: 02 JAN 2018		Name: [Signature]		Date: 02 JAN 2018

<b>Spinneys</b>		<b>سبينيس</b>	
<b>PREQUALIFICATION AND MATERIAL APPROVAL</b>			
Client: AL SEER GROUP	PROJECT: Spinneys HQ & Retail office building		
Consultant: LOCI Architects + consultants	SUBMITTAL NO.: AC/CIVIL/LOCI/PA/236/30		
Contractor: ASHEYANA CONTRACTING L.L.C	REVISION: 00		
Sub-Contractor: <b>DESARCH SCAFFOLDING</b>		Sub-contractor /Manufacturer/Supplier	
<b>FORMWORKS &amp; SCAFFOLDING</b>			
<b>SLABS &amp; BEAMS -TRIZO SYSTEM WITH ALUMINIUM BEAM</b>			
Signed by Subcontractor	Date: 21/01/18		
Signed by Main Contractor	Date:		
Received by Consultant	Date:		
<b>Consultant Comments:</b>			
Refer to the attached comments sheet and also drawings			
<b>RECEIVED</b>			
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved with Comments <input type="checkbox"/> Not Approved, Re-submit			
Approved (A)	Approved As Noted (B)	Re Submit (C)	Rejected (D)
Signed by MEP Engineer	Date:		
Signed by Project Engineer	Date:		
Signed by Resident Engineer	Date:		
Return to Main Contractor	Date:		

<b>PROPOSED RESIDENTIAL BUILDING</b>		<b>ART CONSULTANTS</b>	
Client: CHC Building Contracting LLC		Project No: 491-2015-08	
For: KHALED AHMED QASSIM AL KHATEB (SAFFCO)		REF No: SC-04/3-170	
Plot No: 1031-10111 @ Al Sufyan South East, Dubai, U.A.E		REV No:	
<b>SUPPLIER / SUBCON PRE-QUALIFICATION</b>			
To M/S ART Consultants:			
Please review our technical submittal			
Discipline: <input checked="" type="checkbox"/> Civil/Structural <input checked="" type="checkbox"/> Architecture <input type="checkbox"/> Electrical			
<input type="checkbox"/> Mechanical <input type="checkbox"/> Plumbing <input type="checkbox"/> Others			
Type of Submittal: <input type="checkbox"/> Test <input checked="" type="checkbox"/> Pre-qualification <input type="checkbox"/> Calculations			
Purpose of Submittal: <input checked="" type="checkbox"/> For Approval <input type="checkbox"/> For Information			
Details Of Submittal: SCAFFOLDING			
Manufacturer/SUBCON: M/S DESARCH Building Contracting LLC			
Description: Scaffolding Works			
Report No: -			
Location: -			
Specification Ref. No: -			
<b>Approval Required by:</b>			
CHC Building Contracting LLC		04-Mar-18	
Submitted By: [Signature]		Date:	
<b>ART CONSULTANT'S COMMENTS:</b>			
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved with Comments <input type="checkbox"/> Not Approved, Re-submit			
<b>Comments:</b>			
No objection for M/S Desarch to carry scaffolding works subject to satisfactory safe performance at site. Submit scaffolding safe drawing with design calculation for engineer approval per the manual. Safety certificate shall be obtained for scaffolding activities prior to commencing. Safety tags shall be issued on the scaffolding as it will be erected.			
Stamp & Signature: [Signature]		Date: 05/02/2018	

**Certificate Of Registration**  
Awarded to

**DESARCH BUILDING CONTRACTING LLC**

at  
P.O.BOX NO: 71957, PLOT NO: 8900, STREET-16C, COMMUNITY 613, AL AWEER  
INDUSTRIAL AREA 2, RAS AL KHOR, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS & ISO standard requirements for registration of the management system standard detailed below:

**ISO 9001:2015**  
Quality Management Systems

Scope of work

- > SCAFFOLDING CONTRACTING
- > BUILDING CONTRACTING

IAF 28  
Certificate No: ADU-10150  
Originally Registered: 10 MAR 2023  
Latest Issue: 10 MAR 2023  
Valid up-to: 09 MAR 2026

**WORLDWIDE CERTIFICATION**

This is an accredited certificate authorized for issue by Accreditation Service for Certifying Bodies LLC who have assessed QRS (Pvt.) as a Certifying Body for compliance with ISO 17021:2015 Conformity Assessment - Requirements for bodies providing audit and certification of management systems. This certificate is only valid when confirmed by the register listed in the QRS (Pvt.) (qrs-rl.com)

**UAE OFFICE ADDRESS**  
Quality Registrar Systems Int.  
Abu Dhabi, United Arab Emirates  
www.qrs-rl.com  
Tel: 02-3096156

**Certificate Of Registration**  
Awarded to

**DESARCH BUILDING CONTRACTING LLC**

at  
P.O.BOX NO: 71957, PLOT NO: 8900, STREET-16C, COMMUNITY 613, AL AWEER  
INDUSTRIAL AREA 2, RAS AL KHOR, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS & ISO standard requirements for registration of the management system standard detailed below:

**ISO 14001:2015**  
Environmental Management Systems

Scope of work

- > SCAFFOLDING CONTRACTING
- > BUILDING CONTRACTING

IAF 28  
Certificate No: ADU-20114  
Originally Registered: 10 MAR 2023  
Latest Issue: 10 MAR 2023  
Valid up-to: 09 MAR 2026

**WORLDWIDE CERTIFICATION**

This is an accredited certificate authorized for issue by Accreditation Service for Certifying Bodies LLC who have assessed QRS (Pvt.) as a Certifying Body for compliance with ISO 17021:2015 Conformity Assessment - Requirements for bodies providing audit and certification of management systems. This certificate is only valid when confirmed by the register listed in the QRS (Pvt.) (qrs-rl.com)

**UAE OFFICE ADDRESS**  
Quality Registrar Systems Int.  
Abu Dhabi, United Arab Emirates  
www.qrs-rl.com  
Tel: 02-3096156

**Certificate Of Registration**  
Awarded to

**DESARCH BUILDING CONTRACTING LLC**

at  
P.O.BOX NO: 71957, PLOT NO: 8900, STREET-16C, COMMUNITY 613, AL AWEER  
INDUSTRIAL AREA 2, RAS AL KHOR, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS & ISO standard requirements for registration of the management system standard detailed below:

**ISO 45001:2018**  
Occupational Health and Safety Management Systems

Scope of work

- > SCAFFOLDING CONTRACTING
- > BUILDING CONTRACTING

IAF 28  
Certificate No: ADU-30118  
Originally Registered: 10 MAR 2023  
Latest Issue: 10 MAR 2023  
Valid up-to: 09 MAR 2026

**WORLDWIDE CERTIFICATION**

This is an accredited certificate authorized for issue by Accreditation Service for Certifying Bodies LLC who have assessed QRS (Pvt.) as a Certifying Body for compliance with ISO 17021:2015 Conformity Assessment - Requirements for bodies providing audit and certification of management systems. This certificate is only valid when confirmed by the register listed in the QRS (Pvt.) (qrs-rl.com)

**UAE OFFICE ADDRESS**  
Quality Registrar Systems Int.  
Abu Dhabi, United Arab Emirates  
www.qrs-rl.com  
Tel: 02-3096156

**Certificate Of Registration**  
Awarded to

**DESARCH BUILDING CONTRACTING LLC**

at  
P.O.BOX NO: 71957, PLOT NO: 8900, STREET-16C, COMMUNITY 613, AL AWEER  
INDUSTRIAL AREA 2, RAS AL KHOR, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS & ISO standard requirements for registration of the management system standard detailed below:

**ISO 9001:2015**  
Quality Management Systems

Scope of work

- > SCAFFOLDING CONTRACTING
- > BUILDING CONTRACTING

IAF 28  
Certificate No: ADU-10150  
Originally Registered: 10 MAR 2023  
Latest Issue: 10 MAR 2023  
Valid up-to: 09 MAR 2026

**WORLDWIDE CERTIFICATION**

This is an accredited certificate authorized for issue by Accreditation Service for Certifying Bodies LLC who have assessed QRS (Pvt.) as a Certifying Body for compliance with ISO 17021:2015 Conformity Assessment - Requirements for bodies providing audit and certification of management systems. This certificate is only valid when confirmed by the register listed in the QRS (Pvt.) (qrs-rl.com)

**UAE OFFICE ADDRESS**  
Quality Registrar Systems Int.  
Abu Dhabi, United Arab Emirates  
www.qrs-rl.com  
Tel: 02-3096156



## رخصة تجارية Commercial License

### تفاصيل الرخصة / License Details

License No.	539227	رقم الرخصة
Company Name	DESARCH BUILDING CONTRACTING L.L.C	اسم الشركة
Trade Name	DESARCH BUILDING CONTRACTING L.L.C	الإسم التجاري
Legal Type	Limited Liability Company(LLC)	الشكل القانوني
Expiry Date	02/11/2023	تاريخ الإنتهاء
D&B D-U-N-S ®	534564810	رقم الرخصة الام
Register No.	60915	رقم السجل التجاري
Issue Date	03/11/2002	تاريخ الإصدار
Main License No.	539227	رقم الرخصة الام
DCCI No.	73070	عضوية العرفة

### الاطراف / License Members

Share / الحصص	Role / الصفة	Nationality / الجنسية	Name / الإسم	No./رقم الشخص
	Manager / مدير	India / الهند	سونايل باتهاك بن اس ان باتهاك	149994
			SUNIL PATHAK S N PATHAK	

### نشاط الرخصة التجارية / License Activities

Building Contracting	مقاولات البناء
Scaffolding Contracting	اقامة السقالات
Scaffolding & Formwork Repairing	إصلاح السقالات وقوالب صب الخرسانة

### العنوان / Address

Phone No	971-4-3337012	تليفون	P.O. Box	71957	صندوق بريد
Fax No	971-4-3337154	فاكس	Parcel ID	613-1400	رقم القطعة
Mobile No	971-50-7594342	هاتف متنحرك			البريد الإلكتروني / Email

راس الخور الصناعية الثانية- مكتب رقم 1مك مؤسسه دبي العقاره

### الملاحظات / Remarks

مقاولات البناء (اراضي-اول)

Print Date 10/11/2022 8:32 تاريخ الطباعة Receipt No. 0 رقم الإيصال



الإمارات  
THE EMIRATES

بمكك الآن تجديد رخصتك التجارية من خلال الرسائل النصية القصيرة، أرسل رقم الرخصة إلى 6969 (دو/اتصالات) للحصول على إذن الدفع.  
Now you can renew your trade license by sending a text message (SMS). Send your trade license number to 6969 (Du/ Etisalat) to receive payment voucher.


Get FREE access to Zoho One for the first year  
احصل على زوهو ون مجاناً للشه الأول



وثيقة إلكترونية معتمدة وصادرة بدون توقيع من دائرة الاقتصاد والسياحة في دبي. لمراجعة صحة البيانات الواردة في الرخصة يرجى مسح رمز الاستجابة السريعة this is a certified e-document issued without signature by the department of Economy and Tourism .Kindly Scan the QR Code to Verify the certificate

# STOCKS IN WARE HOUSE







**DESARCH**™  
**SCAFFOLDING**

Head Office  
**DESARCH BUILDING CONTRACTING L.L.C**  
P.O. Box : 71957, Dubai, U.A.E.  
Tel : +971 4 3337012 | Fax: +971 4 3337154

Branch  
**DESARCH BUILDING CONTRACTING L.L.C**  
P.O. Box : 92269, Abu Dhabi, U.A.E.  
Tel : +971 2 5538330 | Fax : +971 2 5538331

E-mail: [desarchscaffolding@gmail.com](mailto:desarchscaffolding@gmail.com), [info@desarchscaffolding.com](mailto:info@desarchscaffolding.com)  
Website : [www.desarchscaffolding.com](http://www.desarchscaffolding.com)





















































